be found. If he removes any quantity above the minimum fixed within the lease period, he shall pay for the excess quantity at tender rates.

(*g*) That he shall abide by such orders as the District Forest Officer may issue regulating the transport of bamboos to and collection at their rafting stations.

(*h*) That he shall abide by the rules of the department, as regards the kindling of fires and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(*i*) That he or his men shall not enter the forest after sunset and before sunrise.

(*j*) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of bamboos removed, and shall keep it open for the examination of Forest Officers above the grade of guards.

(*k*) That he understand that the sale does not prohibit the issue of retail licenses at the seigniorage rates or the exercise by the villagers of their rights in the Forests or the exploitation by the department for supply to Government Departments to the Mysore Paper Mills, Ltd.

(*l*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of the cancellation of contract enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (5) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

Notification dated the 16th August 1936.

It is hereby notified for the information of the public that in addition to the quantities of timber already notified in the *Gazette* for auction sale to be held in Tarikere Depot on the 8th and 9th February 1937, the following additional quantities of timber will be exposed for sale. The conditions of sale are the same as already notified in the *Gazette*.

Beete logs of shipment quality	2,000 c.ft.
Beete logs of 2nd and 3rd quality	2,000 „

M. G. VENKATA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT

KOLAR DIVISION.

Abstract Notification dated 4th January 1937.

The attention of the public is invited to the Notification in pages 50-51 of the issue of the *Mysore Gazette*, dated 14th January 1937, inviting tenders for the work of "Restoring Dadinayakandoddi Jambukere" Register No. 294 of Malur Taluk.

The last date fixed for the receipt of tenders in this Office is 30th January 1937.

Abstract Notification dated 4th January 1937.

The attention of the public is invited to the Notification in pages 48-50 of the issue of the *Mysore Gazette*, dated 14th January 1937, inviting tenders for the work of "Restoring Hulkur Badankere, Register No. 523 of Malur Taluk."

The last date fixed for the receipt of tenders in this Office is 30th January 1937.

P. RAJAGOPALAN,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 14th January 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M. on Monday the 1st February 1937, for urgent repairs to Sree Sringere Mutt at Kudli, Shimoga Taluk. An approximate estimate of quantities is given below.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees ..... in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for urgent repairs to Sree Sringere Mutt at Kudli, Shimoga Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Works should be according to departmental specifications.

14. Transfer of works to other parties or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 1,000 and the work should be completed by the end of May 1937.

16. Cement will be supplied by the Department and the cost with centage recovered.

Abstract estimate for urgent repairs to Sree Sringeri Mutt at Kudli, Shimoga Taluk.

Serial No.	Items of work	Per	Rate as sanctioned	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
	Vidya Sankara Chowki.					
1	Removing mud terrace with planks and connected wood works (*vide* A. B. C. D. in plan) including removing debris out of site and clearing ..	Sqr.	4 0 0	13.61		
2	Dismantling mud walls and removing debris out of premises ..	C/ft.	0 0 2	1,000		
3	Burnt brick in mortar including scaffolding ..	,,	0 4 6	600		
4	Providing and fixing R.C. beaming slab for brick in mud wall ..	,,	1 8 0	28		
5	Cement plastering ½" thick 1:6 ..	Sqr.	5 0 0	13.00		
6	Stone jelly surki concrete, over 3" cement concrete 1:6:12 including cement plastering for proposed granary (at "G" in plan) ..	,,	16 0 0	2.00		
7	Reinforced concrete wall 3" thick at A. B. C. D. ..	C.ft.	1 8 0	248.2		

Serial No.	Items of work	Per	Rate as sanctioned	Quantity	Rate tendered by the contractor	
					In figures	In words
			Rs. a. p.			
8	Providing door in plank terrace for granary including locking arrangements with teak wood ..	S.ft.	1 0 0	24		
9	Retiling the roofing including necessary new country tiles and new bamboos and bamboo reepers including cleaning tiles, etc., complete ..	Sqr.	9 0 0	95·00		
10	T. W. wrought and put up including 2 coats of wood oiling ..	C.ft.	4 8 0	65		
	Brahmanantha Chowki.					
1	Removing the collapsing Balcony in front with terrace and roofing including necessary supporting and scaffolding charges ..	L. S.				
2	Removing damaged mud terrace and ceiling planks and rebuilding as before with necessary good planks, etc., available from the dismantled portion of Vidya Shankara Chowki P. Q. R. S. ..	Sqr.	4 0 0	11·00		
3	Tarring two coats to planks to the sides, in contact with mud terrace ..	,,	2 0 0	11·00		
4	Retiling with available country tiles, etc., including required new country tiles and bamboos and bamboo reepers including cleaning tiles, etc., complete ..	,,	9 0 0	78·20		
5	Plain zinc sheets on teak reepers fixed with bolts and nuts below pot-tiles of verandah leants ..	,,	16 0 0	3·90		
6	T. W. wrought and put up with 2 coats of wood oiling ..	C.ft.	4 8 0	50		
7	Repairs to valleys of roofing with zinc sheets and T. W. planking, complete	R.ft.	1 0 0	100		
	Chandramouleswara Chowki.					
1	Retiling with available country tiles, etc., including necessary new country tiles and bamboos and reepers, etc., complete over roof of Nagar Khana	Sqr.	9 0 0	26·40		
2	Removing the roof of old stores at rear and repairing the roof of cow-shed at left end ..	,,	4 0 0	11·59		
3	Repairs to terrace of Sree Chandramouleswara temple with 3" to 6" brick kappi and 2 courses of flat tiles laid in 1 in 6 cement mortar ..	,,	20 0 0	1·36		
4	Dismantling the old stores and tidying up the site and removing debris out of site ..	S.ft.	0 1 6	380		
5	Repairs to leants roof of verandah inside including new tiles and bamboos, etc.	Sqr.	4 0 0	10·00		

Notification dated 16th January 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M. on Monday the 8th February 1937, for "Restoring Hosagunda Doddakere Reg. No. 1222 of Sagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited Rs. 140 (One hundred and forty only) as earnest money, and be superscribed "Tender for Restoring Hosagunda Doddakere Reg. No. 1222 of Sagar Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc, and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The work should be according to Departmental specifications.

14. Transfer of works to other parties or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 500, and the work should be completed by the end of March 1938.

16. Cement and C. I. pipes will be supplied by the Department and the cost with centage will be recovered.

Abstract estimate for restoring Hosagunda Doddakere, Minor Tank, Register No. 1222 of Saga Taluk.

Sl. No.	Items of work	Per	Rate as sanctioned	Quantity	Rate tendered by contractor	
					In figures	In words
	I. Bund R. L. 57.50.		Rs. a. p.			
1	(*a*) Jungle clearing, cutting and rooting out bamboo bushes on slopes ..	L. S.	..	..		
	(*b*) Removing ant-hills and cutting grips and steps, etc., ...	L. S.	..	..		
2	Earthworks to bund including					

Sl. No.	Items of work	Per	Rate as sanctioned	Quantity	Rate tendered by contractor	
					In figures	In words
			Rs. a. p.			
	watering and tamping with 25 per cent mixture of gravel (earth to be brought from flanks)	C.yd.	0 6 0	1,654		
3	Turfing to tunnel	Sqr.	0 10 0	143·48		
4	Providing and fixing B. M. stones including figuring, painting, etc., complete	Each	4 8 0	2		
5	Providing and fixing register number stone in cement concrete ..	,,	10 0 0	1		
6	Do grade stones ..	,,	2 8 0	9		
7	Do index stones ..	,,	1 0 0	9		
	II. Constructing C.I. pipe sluices at C.S. No. I and C.S. No. IV sill at R.L. 48·25.					
1	Cut opening the bund	C.yd.	0 4 0	88		
2	Earthwork excavation for front head walls	,,	0 4 0	7½		
3	Stone jelly concrete in cement mortar of 1 : 5 : 10 for foundation ..	C.ft.	0 6 0	202		
4	Size stone in cement mortar 1 : 6 ..	C.ft.	0 10 0	166		
5	Providing and fixing cement concrete slab 1 : 2 : 4	,,	1 0 0	6		
6	Providing and fixing burnt stone slabs 4½″ to 6″ thick dressed and fixed ..	S.ft.	1 0 0	20		
7	Drilling holes in orifice slabs ..	Each	1 0 0	3		
8	Providing and fixing C. I. culvert pipe of 6″ dia.	R.ft.	2 8 0	36		
9	Cement plastering ½″ thick 1 : 3 ..	Sqr.	10 0 0	1·50		
10	Removing the damaged masonry of the existing sluices	L. S.	..	..		
11	Refilling earth with 25 per cent of fresh gravel including watering and consolidation	C.yd.	0 3 0	90		
12	Fresh earthwork with 25 per cent mixture of gravel including watering and consolidation	,,	0 6 0	18		
13	Providing and fixing teakwood plug and rod, etc., complete ..	Each	12 0 0	1		
14	Rough stone revetment new ..	C.yd.	3 0 0	5		
	III. Constructing waste weir at R. L. 52·50.					
1	Earthwork excavation for foundation	C.yd.	0 4 0	33		
2	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 6 0	315		
3	Size stone in cement mortar 1 : 6 ..	C.ft.	0 10 0	738		
4	Cement pointing 1 : 3	Sqr.	6 0 0	5·00		
5	Rough stone apron new	C.yd.	2 8 0	61		
6	Approach clearing	L. S.	..	..		

P. SUBBA RAO,
Executive Engineer.